

**THE PHARMACEUTICAL  
CORPORATION (IM) KERALA LIMITED**

**THRISSUR**

**SHORT TENDER DOCUMENT**

Name of Work: Refractory work for 8 ton boiler at Oushadhi Kuttanellur

**THE PHARMACEUTICAL CORPORATION (IM) KERALA LIMITED  
KUTTANELLUR P.O., THRISSUR – 14**

**(A Govt. of Kerala Undertaking)**

**SHORT TENDER NOTICE**

Sealed Super scribed short tenders in the prescribed form are invited from competent, experienced and technically and financially sound contractors for executing the following jobs.

Scope of work	: Refractory work for 8 ton boiler at Oushadhi Kuttanellur
Probable amount of contact	: Rs.246882 + GST
Location of the site	: Kuttanellur, Thrissur

PROFORMA

1. Name of work : Refractory work for 8 ton boiler at  
Oushadhi Kuttanellur
2. Name of tenderer :
3. Address of the tenderer :
4. Telephone No. of the :  
Tenderer if any
5. Details of EMD :
6. Date of commencement of work : 7th day from the date of receipt of letter  
of acceptance or handing over the site  
whichever is later
7. Time of completion : 25 days from the date of commencement of  
Work.
8. Liquidated damages : 0.5% per week of delay. Maximum 10% of executed  
value or contract value whichever is higher

Signature of tenderer

## **GENERAL CONDITION**

1. The short tender shall be submitted in the short tender document purchased from the office or down loaded from the website
2. Last date of submission of short tender is 27/02/2026 3.00 pm and short tender will be opened on the same day 3.30 pm
3. No short tender will be accepted after the stipulated time and date
4. The cost of tender document is Rs.590/-(including 18% GST). Those who wishes to download tender document has to remit the cost of tender document along the tender.
5. The cover containing the short tender should be super scribed with words "Refractory work for 8 ton boiler at Oushadhi Kuttanellur"
6. Cost of tender document and EMD of Rs 7283/- can be remitted in the form of DD drawn in favour of Managing Director Oushadhi, payable at Thrissur or by Cash or by Online(A/c no:**591300590000015**, IFSC:PUNB0591300,Punjab National Bank Kuttanellur Branch) In case the tender cost is remitted by cash, its receipt shall be submitted along with the tender.
7. The entire work should be completed within 25 days from the date of commencement of work.
8. An amount equal to 5% of the quoted amount of work should be remitted by the successful tenderer towards the security deposit which will be released after satisfactory completion of work. E.M.D remitted along with the short tender can be adjusted against the security deposit. If the successful tenderer fails to remit the Security Deposit and execute an agreement in the prescribed format within 7 days from the date of receipt of our letter of acceptance, the short tender is liable to be rejected and the E.M.D remitted should be confiscated.
9. The tenderer should have executed at least one similar nature of work and should submit proof of the same along with the short tender.
10. The rate quoted should be excluding GST.
11. Tenderer should have GST registration and proof of the same should be submitted along with tender document.
12. All materials to be used in the work shall be as per the specification in the BOQ and shall have the specific approval of the site Engineer as to its quality and grade
13. The payment in full will be released after 15 days from the date of submission of final bill after successful completion of the work.
14. Time being the essence of the contract, the time of completion stipulated should be strictly adhered to.
15. If the tenderer fails to complete the work within the period stipulated in the order, Corporation may at their option either (1) recover from the tenderer liquidated damages at the rate of 0.5% of the contract value, for every week or part there of delay subjected to maximum of 10% of the total contract value. (2) Cancel the order wholly or partially and complete it themselves or reassign it to other agency at the risk and cost of the tenderer.

Signature of tenderer.

- 16 The tenderer can visit the work site prior to the submission of the short tender and thereafter no increase in the rate shall be entertained on any ground.
- 17 Any clarification regarding the short tender can be had from the office during the working hours on all working days.
- 18 The short tender shall be kept open for a period of one month from the date of opening for acceptance.
- 19 Managing Director reserves right to accept or reject any or all short tenders or invite fresh short tenders or recheck any of the above conditions without assigning any reason whatsoever. The decision of the Managing Director will be final and binding on all.

Signature of tenderer.

<b>THE PHARMACEUTICAL CORPORATION (I.M) KERALA LTD.</b>					
<b>BOQ</b>					
<b>Name Of Work: Refractory work for 8 TON Boiler at Oushadhi, Kuttanellur</b>					
<b>Item No.</b>	<b>Item Description</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
1	Supply and installation of 76mm thick rock wool of density 100kg/cm <sup>2</sup> for sides of water walls of the boiler by cutting it to fit between framing members, such as joists and studs including all cost of conveyance of all materials, labour lead, lift etc complete as per direction of Engineer-in-charge	m <sup>2</sup>	42		
2	Supply and installation of 25mm thick ceramic blanket of density 120 kg/cm <sup>2</sup> for laying refractory wall and sides of water walls of boiler by cutting it to fit between framing members such as joists and studs with jiggers, fixtures etc including cost and conveyance of all materials, labour, lead, lift etc complete as per direction of Engineer-in-charge	m <sup>2</sup>	63		
3	Brick masonry work using standard fire bricks of size 229mm x 114mm x76mm or nearest available size confirming to IS grade 2042 (2006) for ash sump wall of the furnace using dry set 50 F and mortar white heat -K. refractory mortar including cost and conveyance of all materials labour, lead, lift etc complete as per direction of Engineer-in-charge	m <sup>3</sup>	0.4		

4	Brick masonry work using standard fire block of size 1200mm x600mm x300mm or nearest available size confirming to separation wall inside the furnace using dry set 50 F and mortar white heat -K. refractory mortar including cost and conveyance of all materials labour, lead, lift etc complete as per direction of Engineer-in-charge	m3	1.94		
5	Providing and fixing Oranium sheet of 1.6mm thick for covering of insulation rock wool and ceramic blanket inside the furnace.	m <sup>2</sup>	42		
<b>Total Amount</b>					
<b>GST 18%</b>					
<b>Grand Total</b>					